

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-23161-00-00  
Spot: SENENE Sec/Twnshp/Rge: 14-16S-26W  
4309 feet from S Section Line, 341 feet from E Section Line  
Lease Name: EVEL D Well #: 1  
County: NESS Total Vertical Depth: 4560 feet

Operator License No.: 4689  
Op Name: LUTZ, THOMAS C.  
Address: PO BOX 1766  
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4559	0	WITH 200 SX CMT
SURF	8.625	337		WITH 220 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2016 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KENNY RUPP Company: NORTH FORK SERVICES Phone: (785) 798-5260

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 100# HULLS. PERFORATE AT 2000' & SPOT 50 SX CMT & 100# HULLS. PULL TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2016 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

HAD PUMPED 300 SX CMT DOWN BACKSIDE BUT NO RECORD OF LOG OR TEMPERATURE SURVEY. PERFORATE AT 2000'. RAN TBG TO 4300' & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 1980' & SPOT 25 SX CMT WITH HULLS & 25 SX CMT. PULL TBG TO 1600' & PUMPED 145 SX CMT. DID NOT CIRCULATE. PULL TBG. WILL WAIT TO TOP OFF. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD. 3/21/16: TOPPED OFF WELL WITH 25 SX CMT. CMT WAS DOWN ABOUT 600'. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4381	4386		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed: Michael Maier  
SA (TECHNICIAN)

RECEIVED  
MAR 22 2016  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
MAR 31 2016  
CONSERVATION DIVISION  
WICHITA, KS