

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21540-00-00
Spot: S2S2SW Sec/Twnshp/Rge: 30-16S-29W
325 feet from S Section Line, 3934 feet from E Section Line
Lease Name: DICKEY F Well #: 1
County: LANE Total Vertical Depth: 4585 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 305 N BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4584	0	WITH 175 SX CMT
SURF	8.625	223		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2016 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MARTY ZIEGLER Company: LAVETA OIL & GAS Phone: (620) 546-4559

Proposed Plugging Method: PUMP DOWN 35 SX CMT & 150# HULLS. SPACER TO 2300' & CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/23/2016 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

3/22/16: PUMP 35 SX CMT & 150# HULLS. SPACER TO 2300'. PUMPED 260 SX CMT. NO CMT TO SURFACE. SDON. 3/23/16: TOPPED OFF WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4448	4451		
4363	4367		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL.

Plugged through: CSG

District: 01

Signed

Yam Adams
Yam Adams (TECHNICIAN)

519

KCC WICHITA

APR 01 2016

RECEIVED

RECEIVED
MAR 28 2016
KCC DODGE CITY

Form CP-2/3