

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-031-21625-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 11-23S-14E  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HANNEN B Well #: 5  
County: COFFEY Total Vertical Depth: 1683 feet

Operator License No.: 6227  
Op Name: KRAFT OIL COMPANY LLC  
Address: 434 IRIS RD SW  
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1340		
PROD	4.5	1668		150 SX
PROD	4.5	1678		
SURF	7.5	4		15 SX
SURF	7.5	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2016 8:00 AM  
Plug Co. License No.: 6227 Plug Co. Name: KRAFT OIL COMPANY LLC  
Proposal Rcvd. from: KRAFT OIL COMPANY LLC Company: \_\_\_\_\_ Phone: (620) 836-4570

Proposed Plugging Method: Per KCC District 3 requirements.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2016 10:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

rig up to tubing, pumped 10 sxs cement @ 1265', pulled tubing to 650' pumped 10 sxs cement, pulled tubing to 220' pumped 20sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1289	1298		
<b>RECEIVED KCC DIST # 3 MAR 21 2016 CHANUTE, KS</b>  mH			

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

*no 4-7-16*  
KCC WICHITA  
MAR 25 2016  
Form CP-2/3  
RECEIVED



250 N. Water, Ste 200 - Wichita, Ks 67202

**HURRICANE SERVICES INC**

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer: <b>Kraft Oil LLC</b>		Customer Name:		Ticket No.: <b>100708</b>				
Address: <b>434 Iris Rd. SW</b>		AFE No.:		Date: <b>3/17/2016</b>				
City, State, Zip: <b>Gridley, Ks. 66852</b>		Job type: <b>Plug To Abandon</b>						
Service District: <b>Madison</b>		Well Details: <b>4 1/2" casing</b>						
Well name & No.: <b>Hanner, B # 5</b>		Well Location: <b>11-23-14</b>		County: <b>Coffey</b>	State: <b>Kansas</b>			
Equipment #	Driver	Equipment #	Driver	Equipment #	Hours		AM	TIME
201	Jerry	30	Brad			TRUCK CALLED	PM	
202	Bryan					ARRIVED AT JOB	PM	
106	Mark					START OPERATION	PM	
						FINISH OPERATION	PM	
						RELEASED	PM	
						MILES FROM STATION TO WELL	PM	

**Treatment Summary**

Rig up to 2 3/8", pumped 10 Bbls gel ahead. Spot 20 sks 60/40 pozmix cement w/ 4% gel @ 1265', spot 10 sks 60/40 pozmix cement w/ 4% gel @ 650', set top plug 220' to surface with 20 sks 60/40 pozmix cement w/ 4% gel. Job Complete wash up & tear down "Thank You"

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
c20103	Cement Pump	ea	1.00	\$675.00	\$675.00	\$438.75
p01603	60/40 Pozmix Cement	sack	50.00	\$12.00	\$600.00	\$390.00
p01607	Bentonite Gel	lb	172.00	\$0.30	\$51.60	\$33.54
c00104	Minimum Ton Mile Charge	ea	0.50	\$300.00	\$150.00	\$97.50
c10600	Vacuum Truck 80 bbl	ea	2.00	\$84.00	\$168.00	\$109.20
p01607	Bentonite Gel	lb	250.00	\$0.30	\$75.00	\$48.75

KCC WICHITA  
MAR 25 2016  
RECEIVED

**TERMS:** Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection. Authorization below acknowledges receipt and acceptance of all terms and conditions including the Standard Terms of Sale.

<b>Gross:</b> \$ 1,719.60		<b>Net:</b> \$ 1,117.74
<b>Total Taxable</b> \$ 472.29	<b>Tax Rate:</b> 6.150%	<del>Net: \$ 1,117.74</del>
Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		<b>Sale Tax:</b> \$ 29.05
		<b>Total:</b> \$ 1,146.79

X \_\_\_\_\_  
CUSTOMER AUTHORIZED AGENT

Date of Service: **3/17/2016**  
 HSI Representative: **Brad Butler**  
 Customer Representative:

**Customer Comments or Concerns:**

Hurricane Services appreciates any Comments, Concerns or Criticism's from our valuable customers as Safety and Customer Satisfaction are our Number 1 goal. All Comments are confidential and will be used in a constructive manner to improve our Safety and Job Performance.