

**TO:**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

**API Well Number:** 15-031-20478-00-00  
**Spot:** SESESE **Sec/Twnshp/Rge:** 11-23S-14E  
330 feet from S Section Line, 330 feet from E Section Line  
**Lease Name:** HANNEN B **Well #:** 1  
**County:** COFFEY **Total Vertical Depth:** 1648 feet

**Operator License No.:** 6227  
**Op Name:** KRAFT OIL COMPANY LLC  
**Address:** 434 IRIS RD SW  
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1315		
PROD	4.5	1648		100 SX
SURF	8.625	40		15 SX

**Well Type:** OIL **UIC Docket No:** \_\_\_\_\_ **Date/Time to Plug:** 03/17/2016 10:00 AM  
**Plug Co. License No.:** 6227 **Plug Co. Name:** KRAFT OIL COMPANY LLC  
**Proposal Rcvd. from:** KRAFT OIL COMPANY LLC **Company:** \_\_\_\_\_ **Phone:** (620) 836-4570

**Proposed Plugging Method:** As per KCC District 3 requirements.

**Plugging Proposal Received By:** MICHAEL HEFFERN **WitnessType:** COMPLETE (100%)  
**Date/Time Plugging Completed:** 03/17/2016 12:00 PM **KCC Agent:** MICHAEL HEFFERN

**Actual Plugging Report:**

rig up to tubing,pumped 20 sxs cement @ 1232',pull tubing to 675' , pumped 10 sxs cement,pull tubing to 150' pumped 15 sxs cement to surface,gel spacers between cement plugs.

**Perfs:**

Top	Bot	Thru	Comments
1242	1254		

RECEIVED  
KCC DIST # 3  
MAR 21 2016  
CHANUTE, KS  
MHH

**Remarks:**  
**Plugged through:** TBG

**District:** 03

Signed Mike Deffen  
(TECHNICIAN)

KCC WICHITA  
MAR 25 2016  
RECEIVED

Form CP-2/3  
NO  
4-7-16



250 N. Water, Ste 200 - Wichita, Ks 67202

**HURRICANE SERVICES INC**

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer:	Kraft Oil LLC			Customer Name:		Ticket No.:	100707			
Address:	434 Iris Rd. SW			AFE No.:		Date:	3/17/2016			
City, State, Zip:	Gridley, Ks. 66852			Job type:	Plug To Abandon					
Service District:	Madison			Well Details:	4 1/2" casing					
Well name & No.:	HannerB # 1			Well Location:	11-23-14	County:	Coffey	State:	Kansas	
Equipment #	Driver	Equipment #	Driver	Equipment #	Hours	TRUCK CALLED			AM PM	TIME
201	Jerry	30	Brad			ARRIVED AT JOB			AM PM	
202	Bryan					START OPERATION			AM PM	
106	Mark					FINISH OPERATION			AM PM	
						RELEASED			AM PM	
						MILES FROM STATION TO WELL				

**Treatment Summary**

Rig up to 2 3/8", pumped 10 Bbls gel ahead. Spot 20 sks 60/40 pozmix cement w/ 4% gel @ 1232', spot 10 sks 60/40 pozmix cement w/ 4% gel @ 675', set top plug 150' to surface with 15 sks 60/40 pozmix cement w/ 4% gel. Job Complete wash up & tear down "Thank You"

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
c20103	Cement Pump	ea	1.00	\$675.00	\$675.00	\$438.75
c00101	Heavy Equip. One Way	mi	20.00	\$3.25	\$65.00	\$42.25
p01603	60/40 Pozmix Cement	sack	45.00	\$12.00	\$540.00	\$351.00
p01607	Bentonite Gel	lb	155.00	\$0.30	\$46.50	\$30.23
c00104	Minimum Ton Mile Charge	ea	0.50	\$300.00	\$150.00	\$97.50
c10600	Vacuum Truck 80 bbl	ea	2.00	\$84.00	\$168.00	\$109.20
c00103	Ton Mileage - One way	mi	20.00	\$1.30	\$26.00	\$16.90
p01607	Bentonite Gel	lb	250.00	\$0.30	\$75.00	\$48.75

**KCC WICHITA**  
**MAR 25 2016**  
**RECEIVED**

<p><small>TERMS: Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection. Authorization below acknowledges receipt and acceptance of all terms and conditions including the Standard Terms of Sale.</small></p>	<b>Gross:</b> \$ 1,745.50		<b>Net:</b> \$ 1,134.58
	<b>Total Taxable</b> \$ 429.98	<b>Tax Rate:</b> 6.150%	<del>Net</del>
	Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		<b>Sale Tax:</b> \$ 26.44
			<b>Total:</b> \$ 1,161.02
Date of Service: 3/17/2016			
HSI Representative: Brad Butler			
Customer Representative:			

X \_\_\_\_\_  
CUSTOMER AUTHORIZED AGENT

**Customer Comments or Concerns:**