

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-02802-00-01
Spot: NENWSE Sec/Twnshp/Rge: 12-23S-4W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: TETEN J H Well #: 6
County: RENO Total Vertical Depth: 3433 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	8.625	501		45 SX
PROD	5.5	3433		150 SX
SURF	10.75	490		

Well Type: EOR UIC Docket No: E05368.1 Date/Time to Plug: 12/21/2015 1:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DAVID WILSON Company: KAHAN ASSOC Phone: (620) 960-2560

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 12/21/2015 1:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TRIPPED TUBING TO 3195' PUMPED 65 SX CEMENT 100 LBS HULLS COULD NOT TAG. SET CIBP @ 3175' CAPPED WITH 2 SX CEMENT ON TOP. RAN WIRELINE TO 550' 4 SHOTS FOR PERFS. TRIPPED TUBING TO 550' SPOTTED 35 SX CEMENT WITH 50 LBS HULLS, LEFT OVERNITE, TAGGED IN AM @ 525', PRESSURED UP ON 5.5", CASING HELD PRESSURE. RAN WIRELINE INTO 300' 4 SHOTS FOR PERFS, PUMPED 240 SX CEMENT WITH 50 LBS HULLS, WENT ON VACUUM. 12-21-15, RAN POLY DOWN BACKSIDE TO 350' PUMPED 150 SX CEMENT, THEN RAN POLY DOWN INSIDE 5.5" TO 170' AND FILLED UP WITH 25 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3355	3364		

Remarks: COPELAND CEMENTING OUT OF BURRTON, CLASS A CEMENT USED ON JOB. FAILED MIT.

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 31 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
cc-uic
4-7-16

1/5K