

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-19337-00-00  
Spot: S2NWSENE Sec/Twnshp/Rge: 19-11S-17W  
3490 feet from S Section Line, 990 feet from E Section Line  
Lease Name: PEAVEY UNIT Well #: 9  
County: ELLIS Total Vertical Depth: 3628 feet

Operator License No.: 34559  
Op Name: WM KS ENERGY RESOURCES LLC  
Address: 1001 FANNIN, STE 4000  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3625		100 SX
SURF	8.625	1230		525 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2016 8:00 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: TOM BERENS Company: WM KS ENERGY RESOURCES LLC Phone: (785) 639-5727

Proposed Plugging Method: Ordered 680 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Arb: 3625' - 3628' OH

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2016 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf-Tech Perforated at 1185'. Western Well Service ran in hole with tubing to 3454' and stacked out. Pulled tubing to 3423'. Quality rigged to tubing and pumped 160 sx cement w/350 # hulls mixed in. Pulled tubing to 1830'. Quality rigged to tubing and pumped 320 sx cement w/450 # hulls. Cement circulated up 5 1/2" casing. Ran out of cement on first load 480 sx cement. Ordered another 200 sx cement. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 190 sx cement to circulate cement up 8 5/8" casing. Shut in 8 5/8" casing. Squeezed 5 1/2" and 8 5/8" casings to 500 psi. Shut in pressure 400 psi.

GPS: 39.08352 -099.24426

Perfs:


Top	Bot	Thru	Comments
3625	3628		

Remarks: QUALITY CEMENTING CO TICKET # 1654

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

MAR 22 2016

CONSERVATION DIVISION  
WICHITA, KS

MAR 15 2016

Form CP-2/3

*Handwritten initials and date:*  
MO  
4-7-16