

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-11301-00-01
Spot: SENESE Sec/Twnshp/Rge: 33-34S-2E
1601 feet from S Section Line, 350 feet from E Section Line
Lease Name: CHANDLER B Well #: 1
County: SUMNER Total Vertical Depth: 3520 feet

Operator License No.: 33918
Op Name: WELLSTAR CORPORATION
Address: 11990 GRANT ST STE 550
NORTHGLENN, CO 80233

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2805		
CIBP		3440		
PROD	5.5	3520		100 SX
SURF	8.625	256		155 SX
TI	2.375	2748		

Well Type: EOR UIC Docket No: E26329.1 Date/Time to Plug: 09/01/2015 9:00 AM
Plug Co. License No.: 34733 Plug Co. Name: T & L WELL SERVICE, LLC
Proposal Rcvd. from: PAUL NOBLE Company: WELLSTAR CORPORATION Phone: (303) 280-4511

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/08/2015 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

9/11/15 RAN 2 3/8" TUBING TO 1700' AND SPOT 74 SX OF CEMENT FOR BOTTOM PLUG. RAN BACK IN TO TAG TOP OF CEMENT, UNABLE TO TAG WITH WIRE LINE, COULD NOT GET BELOW 409'. CUT TUBING OFF WITH CHEMICAL CUTTER AT 311' AND PULLED FROM HOLE. 9/8/15 RAN BACK IN 5.5" TO 311' PERFORATED AND CIRCULATE CEMENT UP 8.626 SURFACE CASING WITH A 65-35 POS MIX AND HAD GOOD CIRCULATION TO SURFACE. PLUG JOB COMPLETE. CIBP'S SET @ 2805' AND 3440'.

Perfs:

Top	Bot	Thru	Comments
3457	3461	TBG	
2843	2844	TBG	
2780	2785	TBG	

Remarks: PLUGGING CONTRACTOR AND OPERATOR BELIEVE THE 300 PSI ADDITIVE IN ANNULUS COLLAPSED THE PRODUCTION CASING.

Plugged through: TBG

District: 02

Signed

[Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

CC UIC
no
4-9-16

[Handwritten mark]