

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-22294-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 29-13S-15W  
330 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: DUMLER B Well #: 3  
County: RUSSELL Total Vertical Depth: 3392 feet

Operator License No.: 33996  
Op Name: V. FRANCIS WEIGEL FAMILY PARTNE  
Address: PO BOX 219  
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3417		150 SX
SURF	8.625	745		325 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2016 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JUSTIN L. WEIGEL Company: FRANCIS WEIGEL FAMILY Phone: (785) 324-0180

Proposed  
Plugging  
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement, 9 sx gel and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2016 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1350', 975' and 350'. Ran tubing to 3120' and pumped 9 sx gel followed by 75 sx cement w/150 # hulls. Backside started to circulate. Pulled tubing to 1400' and pumped 125 sx cement. Backside and braden head were circulating water and mud. Pulled tubing to 400' and pumped 60 sx cement. Circulated cement out of backside. POOH. Hooked to casing and pumped 40 sx cement. Good cement circulated out of braden head. Shut in.

GPS: 38.89883 -099.01040

Perfs:

Top	Bot	Thru	Comments
3097	3262		
3069	3073		

Remarks: QUALITY CEMENTING TICKET # 1625

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 04 2016

CONSERVATION DIVISION  
WICHITA, KS

MAR 18 2016

720  
4-7-16

Form CP-2/3