

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23363-00-00  
Spot: SWNWSENW Sec/Twnshp/Rge: 21-26S-5E  
3323 feet from S Section Line, 3642 feet from E Section Line  
Lease Name: WEST KOOGLER Well #: E-4  
County: BUTLER Total Vertical Depth: 2570 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2569		100 SX
SURF	8.625	209		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2015 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/29/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2400', CONSOLIDATED OILWELL SERVICES LOADED HOLE W/38 BBL FLUID, ESTABLISHED CIRCULATION, MIXED & PUMPED 70 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2,079'. RIH W/TBG @ 1500', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A 3% CC. WAITED 2 HOURS, TAGGED CEMENT @ 1991'. PRESSURED CASING @ 200#, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 400'-301'. SWEDGED INTO 5 1/2" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 108 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 2:30 P.M. 10-20-2015. CONSOLIDATED CEMENT TICKET # 48043.

Perfs:

Top	Bot	Thru	Comments
2550	2552	CSG	
2534	2536	CSG	
2510	2512	CSG	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAR 24 2018

CONSERVATION DIVISION  
WICHITA, KS

*SK*

*no 7-16  
4-7-16*