

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22383-00-00
Spot: SWNENW Sec/Twnshp/Rge: 33-8S-19W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: LOWRY Well #: 1
County: ROOKS Total Vertical Depth: 3530 feet

Operator License No.: 32278

String Size Depth (ft) Pulled (ft) Comments

Op Name: TENGASCO, INC.

PROD 5.5 3529 150 SX

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

SURF 8.625 263 160 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/17/2016 9:00 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER WELL SERVICE, INC.

Proposal Revd. from: GARY WAGNER

Company: TENGASCO, INC.

Phone: (785) 625-6374

Proposed Port Collar at 1368' w/300 sx cement.
Plugging Production perforations: 3471' - 3480'.
Method:

Ordered 275 sx 60/40 pozmix 4% gel cement, 500 # hulls and 14 sx gel.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/17/2016 12:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2441'. Quality Oilwell Cementing pumped 10 sx gel followed by 50 sx cement. Pulled tubing to 940' and pumped 75 sx cement w/100 # hulls. Cement circulated. PTOH. Squeezed 115 sx cement. Maximum pressure 1000 psi. Shut in pressure 600 psi. Braden head full of cement.

Perfs:

Top	Bot	Thru	Comments
3480	3484		
3471	3480		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 04 2016

CONSERVATION DIVISION
WICHITA, KS

MAR 21 2016

Form CP-2/3

720
4-7-16