

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21683-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 32-33S-6W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: VALERIE Well #: 1-32  
County: HARPER Total Vertical Depth: 4911 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4911		175 SX
SURF	8.625	280		250 SX
T1	2.875	4492		

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2016 12:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/16/2016 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 5 1/2 CIBP @ 4475', CIRCUALTED CASING WITH PLUG MUD & SPOTTED 10 SX CEMENT ON TOP OF PAKER. TOOH WITH TUBING. SHOT 5.5 CASING OFF AT 1534' AND LAYED OUT. RAN TUBING TO 110' & SPOTTED 35 SX CLASS C CEMENT. PULLED TUBING TO 700' & SPOTTED 35 SX CLASS C CEMENT. PULL TUBING TO 320' AND CIRCUALTED TO SURFACE WITH 105 SX CLASS C CEMENT.

Perfs:

Top	Bot	Thru	Comments
4526	4534	CSG	

Remarks: ORR ENTERPRISES

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
MAR 24 2016 9:00  
CONSERVATION DIVISION  
WICHITA, KS 4-7-16

