

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21684-00-00
Spot: N2S2S2NW Sec/Twnshp/Rge: 6-34S-6W
2210 feet from N Section Line, 1320 feet from W Section Line
Lease Name: KATIE LEE Well #: 1-6
County: HARPER Total Vertical Depth: 4944 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		
PROD	5.5	4944		150 SX
SURF	8.625	270		250 SX
T1	2.875	4469		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/06/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULE & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/11/2016 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 5 1/2 CIBP @ 4500', LOADED HOLE WITH MUD & SPOTTED 10 SX CEMENT ON BP. REC 1506' OF 5 1/2" CASING. RAN TUBING TO 1100' SPOTTED 35 SX CLASS C CEMENT, PULLED TUBING TO 700' SPOTTED. 35 SX CLASS C CEMENT. PULLED TUBING TO 320' & CIRCUALTED CEMENT TO SURFACE WITH 105 SX CLASS C CEMENT.

Perfs:

Top	Bot	Thru	Comments
4860	4870	CSG	
4820	4830	CSG	
4540	4548	CSG	

Remarks: ORR ENTERPRISES

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016 CP-2/3

CONSERVATION DIVISION
WICHITA, KS