

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21913-00-00
Spot: NENW Sec/Twnshp/Rge: 11-34S-8W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: RITTER "E" Well #: #2-11
County: HARPER Total Vertical Depth: 4770 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4767 | | 175 SX |
| SURF | 8.625 | 280 | | 175 SX |
| T1 | 2.875 | 4717 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/10/2016 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4600 & 10 SXS CEMENT. LOAD CASING WITH MUD. SET CIBP AT 4400' & 10 SXS CEMENT. REC CASING FROM 1513', AND PULLED FROM WELLBORE. RAN TUBING TO 1400' & SPOTTED 35 SX CEMENT. PULL TUBING TO 850' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 330' & CIRCULATED CEMENT TO SURFACE WITH 115 SKS CEMENT.


Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4697 | 4710 | CSG | |
| 4688 | 4693 | CSG | |
| 4672 | 4682 | CSG | |
| 4481 | 4487 | CSG | |

Remarks: ORR ENTERPRISES CLASS C CEMENT

Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

Handwritten: No 4-7-16

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

Handwritten: ✓