

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20075-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 9-25S-16W
3465 feet from S Section Line, 4004 feet from E Section Line
Lease Name: MASSEY A Well #: 1
County: EDWARDS Total Vertical Depth: 4350 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4230		WITH 2 SX CMT
PROD	5.5	4344	1499	WITH 125 SX CMT
SURF	8.625	283		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2016 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: CIBP @ 4230' WITH 2 SX CMT. PLUG AT 1080' WITH 13 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/28/2016 3:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4230' & 2 SX CMT. CUT CASING AT 1499' & PULLED. PUMP 13 SX GEL FOLLOWED BY 50 SX CMT AT 1174' THROUGH CASING. PLUG TAGGED AT 870'. 39 SX CMT CIRCULATED FROM 300' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4284	4290		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)
KCC WICHITA

APR 01 2016

RECEIVED

RECEIVED
MAR 30 2016
KCC DODGE CITY

Form CP-2/3

no
4-7-16