

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-20075-00-01  
Spot: NESESE Sec/Twnshp/Rge: 36-27S-13W  
709 feet from S Section Line, 139 feet from E Section Line  
Lease Name: GIBBONS-HESS B Well #: 1  
County: PRATT Total Vertical Depth: 4367 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3680		WITH 2 SX CMT
CIBP		3860		
PROD	5.5	4364	2000	WITH 125 SX CMT
SURF	8.625	240		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2016 12:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 3680' & 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2016 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3680' & PUT 2 SX CMT ON TOP OF CIBP'S THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3732	3736		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
MAR 23 2016  
KCC DODGE CITY

Signed

(TECHNICIAN)

SA

Received  
KANSAS CORPORATION COMMISSION

MAR 31 2016  
CONSERVATION DIVISION  
WICHITA, KS  
Form CP-203  
4-7-16