

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20542-00-00  
Spot: NWNW Sec/Twnshp/Rge: 6-30S-13W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: SHRIVER Well #: 1  
County: BARBER Total Vertical Depth: 4740 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4590	0	WITH 150 SX CMT
SURF	10.75	268		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2016 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SPOT HULLS & 50 SX CMT AT 4500' THROUGH TBG. PERFORATE 4 1/2" CASING AT 800'. RUN TBG TO 800' TO PLUG THROUGH. FILL 4 1/2" CASING & 4 1/2" X 10 3/4" ANNULUS WITH CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/17/2016 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SPOT 150# HULLS & 50 SX CMT THROUGH TBG AT 4518'. LET CMT SET. TAG TOC @ 3500'. PERFORATE 4 1/2" CASING AT 800'. RUN TBG IN TO 800'. PUMPED DOWN TBG WITH CMT. AFTER 200 SX CMT PUMPED CMT CIRCULATED TO SURFACE IN 4 1/2" CASING. SHUT 4 1/2" CASING IN. HAD RETURNS UP 4 1/2" BY 10 3/4" ANNULUS. AFTER PUMPING THE REMAINING 150 SX CMT LOST RETURNS UP ANNULUS. PULLED TBG OUT OF HOLE & TOP OFF 4 1/2" CASING WITH 10 SX CMT. HOLE ON VACUUM. SDON. 3/17/16: TAG TOC @ 800'. PERFORATE 4 1/2" CASING AT 300'. RUN IN HOLE WITH 300' OF TBG. PUMPED DOWN TBG WITH 25 SX CMT CIRCULATING CMT TO SURFACE INSIDE OF 4 1/2" CASING. SHUT IN 4 1/2" CASING. COULDN'T PUMP INTO 4 1/2" X 10 3/4" ANNULUS. LAY TBG DOWN. TIED ONTO 4 1/2" X 10 3/4" ANNULUS. PUMPED 15 SX CMT DOWN ANNULUS. PRESSURED TO 200# HELD.

Perfs:


Top	Bot	Thru	Comments
4501	4540		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)  
SA

Received  
KANSAS CORPORATION COMMISSION CP-2/3

MAR 31 2016

CONSERVATION DIVISION  
WICHITA, KS

70-7-16