

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23614-00-01
Spot: NESENWNW Sec/Twnshp/Rge: 16-34S-3E
4390 feet from S Section Line, 4006 feet from E Section Line
Lease Name: JIMMERSON Well #: 1
County: COWLEY Total Vertical Depth: 3404 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3404		300 SX
SURF	8.625	305		200 SX

Well Type: EOR UIC Docket No: E26179.1 Date/Time to Plug: 01/15/2016 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 3230 W/ 4 SXS, PERF & CIRC. 355'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 01/18/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 3200', QUALITY WELL SERVICE MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL 3% CC 150# HULLS & DISPLACED IN CASING. 1-18-2016, RIH ON WIRELINE PERFORATED SQUEEZE HOLES 355'-356'. RIH W/TBG @ 360, QUALITY WELL SERVICE MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL 3% CC. LAYED TUBING DOWN, SWEDGED INTO 4.5" CASING, QUALITY WELL SERVICE MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE 1/18/2016 5:00 PM.

Perfs:

Top	Bot	Thru	Comments
3291	3301		CSG
3282	3284		CSG

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

NO
CC-MIC
4-9-16

SK