

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-24194-00-00  
Spot: SWNE Sec/Twnshp/Rge: 11-14S-19W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: STADELMAN Well #: 3  
County: ELLIS Total Vertical Depth: 3900 feet

Operator License No.: 33723  
Op Name: PAUL BOWMAN OIL TRUST  
Address: 606 CEDAR STREET  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3899		575 SX
SURF	8.625	285		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2016 8:30 AM  
Plug Co. License No.: 33723 Plug Co. Name: PAUL BOWMAN OIL TRUST  
Proposal Rcvd. from: DONALD A. BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Plugging Method: Ordered 345 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
4 1/2" casing circulated cement top to bottom.  
LK: 3662' - 3696', OA

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2016 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3610'. Swift rigged to tubing, mixed and pumped 100 sx cement w/360 # hulls. Pulled tubing to 2067'. Rigged to tubing and pumped 190 sx cement w/250 # hulls. Pulled tubing. Rigged to 4 1/2" casing and pumped 45 sx cement to fill hole with cement. 4 1/2" casing standing full. Rigged to 8 5/8" surface casing and pumped 10 sx cement w/150 psi. Shut in pressure 150 psi.

GPS: 38.85379 -099.39558

Perfs:


Top	Bot	Thru	Comments
3662	3696		

Remarks: SWIFT SERVICES TICKET # 28775

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

cm

Received  
KANSAS CORPORATION COMMISSION

MAR 22 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

MAR 15 2016

no  
4-7-16