

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-00886-00-03
Spot: NESENW Sec/Twnshp/Rge: 22-10S-23W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GRIFFITH P Well #: 5
County: GRAHAM Total Vertical Depth: 1963 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1954		425 SX
SURF	8.625	253		175 SX

Well Type: SWD UIC Docket No: D30928.0 Date/Time to Plug: 02/23/2016 11:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Perforations from 1480' to 1640'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2016 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1446' and pumped 75 sx cement w/100 # hulls. Good circulation of cement.
Pulled tubing out. Squeezed casing w/20 sx cement. Shut in pressure 400 psi. Tied on to
backside and squeezed w/10 sx cement. Shut in pressure 300 psi.

GPS: 39.17119 -099.87640

Perfs:

Top	Bot	Thru	Comments
1480	1640		

Remarks: CONSOLIDATED CEMENT TICKET # 49657

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

MAR 01 2016

Received
KANSAS CORPORATION COMMISSION

MAR 22 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no uic
cc 4-7-16