

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20706-00-00
Spot: NENENW Sec/Twnshp/Rge: 11-33S-31W
5031 feet from S Section Line, 2890 feet from E Section Line
Lease Name: LEPPER Well #: 1-11
County: SEWARD Total Vertical Depth: 6000 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
CIBP		4850		
PROD	4.5	5053	1720	WITH 200 SX CMT
SURF	8.625	1638		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2016 9:00 AM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: BILL DYSART Company: HUNNINGTON ENERGY Phone: (806) 202-0046

Proposed Plugging Method: CIBP @ 4620' WITH 2 SX CMT. PLUG AT 1660' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2016 3:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 4620' WITH 2 SX CMT. 1ST PLUG AT 1694' WITH 50 SX CMT. 2ND PLUG AT 548' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 20 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4898	4899		
4670	4673		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED CLASS C CEMENT BY PARTNERS OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed B. V.

Received W
KANSAS CORPORATION COMMISSION
4-7-16

RECEIVED
MAR 22 2016
KCC DODGE CITY

(TECHNICIAN)

MAR 31 2016
Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS