

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21166-00-00
Spot: SESENEW Sec/Twnshp/Rge: 21-17S-34W
1081 feet from N Section Line, 2465 feet from W Section Line
Lease Name: J & B WILKINSON Well #: 1
County: SCOTT Total Vertical Depth: 4900 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	345		WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/15/2016 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2380' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 03/15/2016 2:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report: _____ Perfs: _____

1ST PLUG AT 2380' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY.
Plugged through: DP

District: 01

Signed: Michael Maier
SA (TECHNICIAN)

RECEIVED
MAR 22 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
MAR 31 2016
CONSERVATION DIVISION
WICHITA, KS