

DISTRICT CONSERVATION AGENT'S REPORT

VO

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 44-28

LOCATION SE 1/4 - 2E - 2E

SEC. 1 TWP. 14 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease C.M. Krey

Operator W. J. H. Tathach Address #111 S, Topeka-Wichita-Haus.

Field _____ County Stafford

Total Depth 3732 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 325 ft. Circulated with cement.
7 casing set at 3704 ft. Cemented with 200 sacks cement.
Plugged back to 3700 ft with shot - dumped 6 sacks
of cement at 3700 ft - Ripped off & pulled the 7 casing.
Mud to 300 ft - Set Back Bridge & 20 sacks of
cement at 300 ft - Mud to 36 ft - Bridge &
10 sacks of cement at the surface.
Bill Morgan - Plugging Contractor -

RECEIVED
STATE CORPORATION COMMISSION

1-8-51

PLUGGING
FILE SEC 1 TWP 14 RGE 11W
BOOK 44 PAGE 28 LINE 28

C. W. Tough
District Conservation Agent
Date 1-3-51