



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 92-30

LOCATION C 27 1/2 - SE - SW

SEC. 2 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Anna Turner

Operator Deep Rock Oil Corp Address Box # 429 - Hutchinson - Kans.

Field _____ County Stafford

Total Depth 3766 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 250 ft. Circulated with cement.
7" casing set at 3703 ft. Filled back down bottom
to 3700 ft with chat - Dumped 6 sacks of cement at
3700 ft. Shot oil & Pulled the 7" casing. Filled with
mud to 250 ft. 10 Brides & 20 sacks of cement at 250 ft.
Mud to 36 ft. Plug & 10 sacks cement at the surface
Bill Morgan - Plugging Contractor -

RECEIVED

Conservation Div.

C. D. Stout

District Conservation Agent

PLUGGING
MAY 26 1949
SEC 2 TWP 24 RGE 11W
CORPORATION
COMMISSION
KANSAS

MAY 26 1949

CORPORATION Date

5-24-49

COMMISSION
KANSAS

5-26-49