

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21857-0000

LEASE NAME Kelly #1

WELL NUMBER _____

SPOT LOCATION C NE SW

SEC. 8 TWP. 24S RGE. 11W or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 8/15/84

Plugging Completed 8/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Energy, Inc.

ADDRESS 415 First Nat'l Bank Bldg, 105 N. Main, Wichita, Ks.
67202

PHONE # (316) 265-2661 OPERATORS LICENSE NO. 5230

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	282'	none
				5 1/2"	3829'	2882'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3722' & 5 sacks cement. Shot pipe at 2925' & 2882'.
Pulled total of 71 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement,
10 gel, 1 hull, 8 5/8 plug, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1984



Irene Hoover
Notary Public

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1984

CONSERVATION DIVISION
Wichita, Kansas