

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 7 Twp. 24 Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

C W/2 E/2 NE/4
Lease Owner P. V. Properties, Inc.
Lease Name SLADE Well No. #1

Office Address 360 Sutton Place Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed 4-2 1981
Application for plugging filed 4-2 1981
Application for plugging approved 4-2 1981
Plugging commenced 4-3 1981
Plugging completed 4-3 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3780'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 500' w/40 sacks 50/50 pozmix thru drill pipe
Middle plug set at 270' w/30 sacks " " thru drill pipe.
Top plug at 40' w/solid bridge - $\frac{1}{2}$ sack hulls & 10 sacks cement
10 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
P.O. Box 823 Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 81

My commission expires 4-11-1982

Deborah M. Stinebaugh
Notary Public.

RECEIVED
APR - 7 1981
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: March 28, 1981
 DATE COMPLETED: April 3, 1981

F. V. Properties, Inc.
 SLADE #1
 C W/2 E/2 NE/4
 Sec. 7, T24S. R11W
 Stafford County, Ks.

0 - 30'	Top Soil
30 - 110'	Sand, Shale
110 - 2910'	Shale, Lime
2910 - 3221'	Lime
3221 - 3241'	Shale & Lime
3241 - 3255'	Lime
3255 - 3370'	Shale
3370 - 3776'	Lime & Shale
3776 - 3780'	Chert, Lime, Shale
3780'	RTD

ELEVATION: 1840 K.B.

FORMATION DATA

Anhydrite	597'
Topeka	2910'
Hoebner	3221'
Toronto	3241'
Douglas	3255'
Br. Lime	3370'
Landing K.G.	3403'
Viola	3776'
RTD	3780'

Surface Pipe: Set new 8-5/8",
 28# pipe at 271' w/185 sacks
 60/40 pozmix, 2% gel, 3% cc.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
 statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 6th day of April 1981.

My Comm. Expires:

4-11-1982

Alexis M. Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

APR - 7 1981

CONSERVATION DIVISION
 Wichita, Kansas