


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 9 Twp. 24 Rge. 11 (E) W. (W)  
Location as "NE/CNW%SW%" or footage from lines 660' N. & 990' E. of W/4 Cor.  
Lease Owner Cities Service Oil Company  
Lease Name Figger Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed February 26, 19 44  
Application for plugging filed February 8, 19 56  
Application for plugging approved February 9, 19 56  
Plugging commenced February 21, 19 56  
Plugging completed February 25, 19 56  
Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production February 11, 19 56  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege  
Producing formation Viola Depth to top 3774 Bottom 3781 Total Depth of Well 3781 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	3776'	1798'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3781-3765', sand.  
3765-3725', 5 sacks cement.  
3725- 275', mud.  
275- 235', rock bridge and 10 sacks cement.  
235- 20', mud.  
20' to base of cellar, 5 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 3 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Wilson, Inc. - Chas. D. Wilson, Operator  
Address 2921 Bonita, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover  
Box 751, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 56

W. G. Smith  
Notary Public.

My commission expires March 12, 1959.

24-7360 3-53-20M

**PLUGGING**  
FILE SEC 9 T 24 R 11 W  
BOOK PAGE 37 LINE 29

Company Nitias Service Oil Co. Well No. 1 Farm Wagon  
 Location 660' North and 990' East of 1/4 corner Sec. 9 T. 24 R. 11E  
 Elevation 1825 County Stafford State Kansas  
 Initial Prod. 100' Gauge Potential: 3000 oil, no water, contractor Corbett-Barbour Drilg. Co.  
24 hrs. (Indicated capacity 4833 bbls.)  
 Acid None Drlg. Comm. February 13, 1944  
 T. D. 1781' Drlg. Comp. February 26, 1944

SAGGING RECORD:

8-5/8" @ 255' cen. 100 sx bulk and  
 50 sx Lehigh cement  
 5-1/2" @ 376' cen. 100 sx Portland  
 cement

FORMATION LOGGED:

surface sand	0-100
red bed & shells	400
shale & shells	955
lime shells & shale	1260
shale & shells	1445
broken lime	1565
shale & lime	1710
lime	1775
lime & shale	1920
lime	2075
lime & shale	2195
lime	2250
shale	2525
shale & lime	2660
shale	2910
lime	3468
chert	3480
lime	3545
lime & shale	3707
shale	3753
shale & lime	3781
lime	3784

3784 Rot. "B" = 3781 612

Curr. Top Viola	3774'
Penetration	7'
Total Depth	3781'

Fillup: 3000' oil in 4 hours  
 Hole full oil in 9 1/2 hrs.

Slope Test (Acid Bottle):

1000'	OK
1500'	OK
2000'	OK
2500'	OK
3000'	OK
3500'	OK

**PLUGGING**  
 FILE SEC 9 T 24 R 11W  
 BOOK PAGE 37 LINE 29