

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-20

2-010070

API NUMBER: 15-

155-01661-0000
10-13-57

NE SW NW, SECTION 1 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5526

3620

FEET FROM S SECTION LINE

4290

FEET FROM E SECTION LINE

OPERATOR HAROLD J MILBURN

NAME & 7315 NORTH MONROE

ADDRESS HUTCHINSON KS 67502

LEASE NAME: HAURY #1

COUNTY: RENO

WELL TOTAL DEPTH: 3620' (3413')

PIPE:

SURFACE CASING: 8-5/8" @ 667'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SMD ☐ RECEIVED
KANSAS CORPORATION COMMISSION

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: BOX 209, CHASE KS 67524

LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 20 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: HAROLD J MILBURN

COMPANY NAME: HAROLD J MILBURN

PHONE: 316-663-1616

WERE: SAND 3265' & TOP W/5 SX CMT - SHOOT PIPE OFF - PULL
PIPE TO 720' & SPOT W/50 SX CMT - PULL PIPE TO 350' &
CIRC CMT TO SURF
5-1/2" CSG @ 3680' - PERFS 3316' TO 3339'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (☐) PART (☒) NONE (☐)

COMPLETED: HOUR: 12:00 DAY: 20 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:

SANDED TO 3265' & TOPPED W/5 SX CMT - SHOT PIPE OFF
@ 2127' - PULLED PIPE BUT PIPE PARTED - PULLED 479' OF
5-1/2" CSG - RAN 1" TUB TO 480' & CIRC 135 SX CMT TO
SURF

RETRIVED 479' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #1879

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE MAR 14 1995

INV. NO. 42367

Michael R. Wilson

(AGENT)

FORM CP-2/3
REV. 3/90