

2-22

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-20,821-⁰⁰⁰E-10,414

E2 SE NW, SECTION 1 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5526 3360 FEET FROM S SECTION LINE
3080 FEET FROM E SECTION LINE

OPERATOR HAROLD J MILBURN
NAME & 7315 NORTH MONROE
ADDRESS HUTCHINSON KS 67502

LEASE NAME: HAURY #4
COUNTY: RENO
WELL TOTAL DEPTH: 3400'

110.50

PIPE:

SURFACE CASING: 12-3/4" @ 310 RECEIVED
KANSAS CORPORATION COMMISSION

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL X SMD _____ D&A _____
MAR 13 1995

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC CONSERVATION DIVISION
ADDRESS: BOX 209, CHASE KS 67524 LICENSE: 31529 WICHITA, KS

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 22 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: HAROLD J MILBURN
COMPANY NAME: HAROLD J MILBURN PHONE: 316-663-1616

WERE: SAND TO 3340' & TOP W/4 SX CMT - SHOOT PIPE
OFF - PULL PIPE TO 575' & SPOT 35 SX CMT - PULL
PIPE TO 360' & CIRC CMT TO SURF
4-1/2" CSG @ 3398' - PERFS 3390' TO 3394'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 14:00 DAY: 22 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED TO 3340' & TOPPED W/4 SX CMT - SHOT PIPE OFF
@ 2028' - PULLED PIPE TO 626' & SPOTTED 35 SX CMT, 200
LBS HULLS - PULLED PIPE TO 376' & CIRC 240 SX CMT & 100
LBS HULLS TO SURF

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #1912

I DID OBSERVE THIS PLUGGING.

INVOICED
MAR 14 1995

Michael R. Wilson
Michael R. Wilson (AGENT)

DATE

INV. NO. 42368