

3-21

2-080027

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-20,604-0000

SE SE NW, SECTION 1 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5526

2970' FEET FROM S SECTION LINE  
2970' FEET FROM E SECTION LINE

OPERATOR Harold J. Milburn  
NAME & 7315 N. Monroe  
ADDRESS Hutchinson, KS 67502

LEASE NAME: Haury #3

COUNTY: Reno 110.17  
WELL TOTAL DEPTH: 3390'

CONDUCTOR PIPE: 12-3/4 @ 315'

SURFACE CASING: 8-5/8 @ 617'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 21 MONTH: 3 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: H. Milburn  
COMPANY NAME: Harold J. Milburn PHONE: 316-663-1616

WERE: Sand back to 3300' - dump bail 5 sx - shoot off pipe -  
plug thru 5-1/2" 3 sx hulls, 35 sx cmt @ 680' - 100 sx  
@ 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 2:00 DAY: 21 MONTH: 3 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded to 3300' - 5 sx - shot 5-1/2" @ 2408' -  
680' - sanded back to 3300' - dump bailed 5 sx cmt -  
shot off pipe @ 2408' - pulled up to 680' - balanced a  
plug of 50# hulls, 35 sx cmt - pulled up to 300' and  
circ thru 5-1/2" - cmt to surface.

REMARKS: Halliburton #125418

**INVOICED**

I DID OBSERVE THIS PLUGGING.

DATE 4-11-91

INV. NO. 31489

APR 4 1991

Doug Louis  
Doug Louis (AGENT)

FORM CP-2/3  
REV. 3/90

CONSERVATION DIVISION  
Wichita, Kansas

DW