

TO: 1041364
STATE CORPORATION COMMISSION

8-13

API NUMBER 15-185-22,411-0000
C W/2 SW NE SEC. 27, T 24 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME TUCKER WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 9482 WELL TOTAL DEPTH 4240 FEET

137.80

OPERATOR: NATIONAL PETROLEUM RESERVES PRODUCTION CSG: SIZE 5 1/2" @ 4236' WITH 170 SX

NAME AND ADDRESS 260 N ROCK RD, SUITE 130 SURFACE CASING: SIZE 8 5/8" @ 321' WITH 225 SX

WICHITA, KS 67206-2241

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 13 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED FUCHS W/SWIFT SERVICES

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4191-96

SANDED BACK TO 4150' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS & 125 SX CEMENT. MAXIMUM PSI @ 450. SHUT IN WITH 0.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:40 PM DAY: 13 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 4150' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS & 125 SX CEMENT. MAXIMUM PSI @ 450. SHUT IN WITH 0.

STATE CORPORATION COMMISSION

AUG 30 1999

8-30-99

CONSERVATION DIVISION

Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2500' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

(DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CH-2/B

DATE 8-31-99

INV. NO. 60447

INVOICED