

To: 1 070437
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-11-87
API NUMBER 15- 185-22,467-0000

TECHNICIAN'S PLUGGING REPORT

NE NE SW, SEC. 27, T. 24 S, R. 14 W/E
2310 feet from S section line
2970 feet from E section line

Operator License # 9740

Lease Name Koelsch Well # 1-27

Operator: Petro Locators, Inc.
Name & Address P.O. Box 77
Pratt, KS 67124

County Stafford 138.78

Well Total Depth 4270 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address Box 823, Great Bend, KS 67530

Company to plug at: Hour: 12:40 p.m. Day: 11 Month: 10 Year: 19 87

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1973'
Anhydrite 875-901'

1st plug at 900' with 40 sx cement,

2nd plug at 290' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:55 p.m. Day: 11 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 900' with 40 sx cement,

2nd plug at 290' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied. CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging.

Signed Dan Gooden
(TECHNICIAN)

DATE 10-14-87

INV. NO. 18496

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. October 2, 1987

API Number 15-185-22, 467-0000

OPERATOR: License # 9740
Name PETRO LOCATORS, INC.
Address P. O., Box 77
City-State/Zip Pratt, Kansas 67124
Contact Person Clarence Michael
Phone 316/672-3040

NE NE SW Sec. 27 Twp. 24 S, Rg. 14
2310 Ft. from South Line of Section
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Stafford
Lease Name Koelsch Well # 1-27
Ground surface elevation cat 1960 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 180
Depth to bottom of usable water 180
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 250
Conductor pipe required
Projected Total Depth 4195 feet

CONTRACTOR: License # 5929
Name DUKE DRILLING CO., INC. Box 823
City-State Great Bend, Kansas 67530

Well Drilled For: Well Class: Type Equipment:
X Oil Storage X Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date September 30, 1987 Signature of Operator or Agent Sally R. Byers Title Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.
This Authorization Expires 3-30-88 Approved By 9-30-87

EFFECTIVE DATE: 10-4-87

Spud 10-3-87 878-250

NE NE SW Sec. 27 Twp. 24 S, Rg. 14
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

60/40 Poz 670 Mel Plug water well top to bottom

1st plug @ ft. deep TOP of Arbuckle or formation with 80sx feet of 60/40 Pozmix, 6% gel
2nd plug @ ft. deep Base Anhydrite or formation with 40sx feet of
3rd plug @ ft. deep 30' below 8-5/8" or formation with 40sx feet of
4th plug @ ft. deep 40' or formation with 10sx feet of
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet 15 SX (b) Mousehole to surface minus 5 feet

PUSHER Leonard Williamson
TD 4270 FORMATION Arbuckle
SURFACE PIPE 259' @ 8 5/8"
ANHYDRITE 875' ELEVATION 1973'
STARTING TIME & DATE 12:40 PM 10-11-87
COMPLETION TIME & DATE 1:55 PM
1st PLUG @ 900 FT. W/ 40 SX
2nd PLUG @ 290 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Filled
CEMENT COMPANY Allied
TECHNICIAN D.G.

allied-if plug well

RECEIVED STATE CORPORATION COMMISSION

OCT 13 1987

CONSERVATION DIVISION Wichita, Kansas