

To: <sup>1</sup> 120735  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-16 API NUMBER 15-185-22,444-0000  
NE SE NW, SEC. 27, T. 24 S, R. 14 W  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482  
Operator: National Petroleum Reserves, Inc.  
Name & Address: 250 N. Rock Rd., Ste. 340  
Wichita, KS 67206

Lease Name Neill Well # 1  
County Stafford 138.45  
Well Total Depth 4260 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 16 Month: 9 Year: 1992

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4258' w/165 sx cement, Perfs at 4211-13, 4130-38'

1st plug sand back to 4100' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 16 Month: 9 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2380' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1992  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

I (did ~~not~~) observe this plugging.

DATE 9-24-92

Signed Duane Rankin (TECHNICIAN)

INV. NO. 36252