

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185- 21,625-0000

SW SW SE , Sec. 28 , T 24 S, R 14 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5771

Lease Name Turner Well # 1

Operator: R & D Petroleum  
Name & P. O. Box 298  
Address Hoisington, KS 67544

County Stafford

Well Total Depth 4340 feet 141.05

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 16 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4338 Perfs 3908 - 14 PBT 4150

1st plug pump 30 sx cement on bottom - plug went on vacuum

2nd plug pump 40 sx cement at 3800'

Top plug 3 sx hulls 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release

8 5/8" rubber plug and pump an additional 125 sx cement

Maximum pressure 700# and shut-in pressure 350#

Signed *Stew Churnett*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 am Day: 16 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4338 Perfs 3908 - 14 PBT 4150

1st plug pump 30 sx cement on bottom - plug went on vacuum, 2nd plug pump 40 sx

cement at 3800', top plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1

sack hulls and release 8 5/8" rubber plug and pump an additional 125 sx cement

Maximum pressure 700# and shut-in pressure 350#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 2164' of 4 1/2" casing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 3-23-84

INV. NO. 0913

3-16

RECEIVED STATE CORPORATION COMMISSION

MAR 21 1984

CONSERVATION DIVISION Wichita, Kansas

Signed *Stew Churnett*  
(TECHNICIAN)