

1080404

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Comp. 2-20-63

S/2 SW, SEC. 23, T 24 S, R 14 W/4E

990 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Koelsch Well # 2

Operator: Nadel and Gussman

County Stafford 138.45

Name & Address 3232 First National Tower

Well Total Depth 4260 feet

Tulsa, OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 am Day: 25 Month: July Year: 1985

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 4165' Perfs at 3764-67', 3755-57', 3750-52', 3760-36' (Lansing K.C.)

1st plug sand back to 3680' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Orders given by Paul A. Luthi

Plugging Proposal Received by *J. N. Neff* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:10 pm Day: 25 Month: July Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2014' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 06 1985

INV. NO. 9336

RECEIVED
STATE CORPORATION COMMISSION
Signed

AUG 2 1985

J. N. Neff
(TECHNICIAN)