

9-22

1 040166

API NUMBER 15-185-22,525-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 100' W NE SW, SEC. 23, T 24 S, R 14 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line

3400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097

Lease Name Koelsch Well # 1

Operator: Martin Oil Producers, Inc.

County Stafford 136.50

Name & Address 1010 Union Center

Well Total Depth 4200 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated never produced

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 4:45 p.m. Day: 22 Month: RECEIVED 9 Year: 1988

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4197' PBDT 4139' Perfs at 3976-84'

1st plug set CIBP with 1 sx cement on top,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 p.m. Day: 22 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3938' and put 2 sx cement on top of CIBP with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 8 5/8" wiper plug and 100 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2007' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 10-6-88

Signed Stephen J. Pfeifer
(TECHNICIAN)

WV. NO. 22527