

1080405

Docket No. E-15,408

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 10-8-64

C W/2 NE SW, SEC. 23, T 24 S, R 14 W/E

1980 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Koelsch Well # 3

Operator: Nadel and Gussman

County Stafford 136.31

Name & Address 3232 First National Tower

Well Total Depth 4194 feet

Tulsa, OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

application was approved to convert to injection but conversion never took place

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address P. O. Box 31, Russell, KS 67665

Company to plug at: Hour: 12:45 pm Day: 25 Month: July Year: 1985

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 4200' squeezed at 759' with 300 sx cement - cement circulated to surface.

Perfs at 3742-47' (Lansing K.C.)

Squeeze well with 3 sx hulls, 50 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Orders given by Paul A. Luthi

Plugging Proposal Received by *J. A. Neff* (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 25 Month: July Year: 1985

ACTUAL PLUGGING REPORT 1st plug squeezed well with 3 sx hulls, 50 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement.

Maximum pressure 800 psi and shut in 800

Remarks: Used 60/40 Pozmix 6% gel by Allied. No Recovery

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 06 1985

INV. NO. 9334

RECEIVED STATE CORPORATION COMMISSION

Signed

AUG 2 1985 8-2-85

J. A. Neff (TECHNICIAN)