

To: 1,070027  
STATE CORPORATION COMMISSION  
Wichita, State Office Bldg. - PLUGGING SECTION App.  
130 S. Market, Room 2078  
Wichita, KS 67202

10-3  
API NUMBER 15- Docket #E-12,893 15-185-30363-10-20  
NW NW NW, SEC. 15, T 24 S, R 11 WXE  
5130 feet from S section line  
4980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860  
Operator: Castle Resources Inc.  
Name & Address: P.O. Box 87  
Schoenchen, KS 67667

Lease Name Zenith Unit Well # 4-W  
County Stafford 125.84  
Well Total Depth 3872 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor United Cementing License Number 30437  
Address P.O. Box 712, El Dorado, KS 67042

Company to plug at: Hour: 11:45 a.m. Day: 3 Month: 10 Year: 19 97

Plugging proposal received from Jerry Green  
(company name) Castle Resources Inc. (phone) 785-625-5155

work: 5 1/2" at 3826' w/110 sx cement, Open hole 3826-72'

1st plug sand back to 3775' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 125 sx cement.

Plugging Proposal Received by Scott Alberg  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 3 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3775' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 250 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by United Cementing. Recovered 2200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED  
DATE OCT 23 1997  
INV. NO. 4925

Signed [Signature] (TECHNICIAN)