

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22154-00-01  
Spot: CE2 Sec/Twnshp/Rge: 1-24S-11W  
2640 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: ZENITH WATERFLOOD UN Well Number: 24  
County: STAFFORD Total Vertical Depth: 3808 feet

Operator License No.: 32699  
Op Name: ZU, LLC  
Address: 108 WEST 34TH  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3838 WITH 175 SX CMT <sup>123.76</sup>  
Surface Casing Size: 8.625 feet: 250 WITH 175 SX CMT

Well Type: EOR UIC Docket No: E12893.14 Date/Time to Plug: 03/13/2003 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3480' & 6 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 8 5/8" WIPER PLUG - 100# HULLS - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/13/2003 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3709-18'. SANDED TO 3480' & 6 SX CMT WITH DUMP BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 8 5/8" WIPER PLUG - 100# HULLS - 100 SX CMT. MAXIMUM PRESSURE 500 PSIG. INITIAL SHUT IN PRESSURE 300 PSIG.

RECEIVED  
KANSAS CORPORATION COMMISSION


APR 02 2003

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2020' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 4-3-03

INV. NO. 2003061374

Form CP-23