

1080193

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,857-0000

C NE SW, SEC. 8, T 24 S, R 11 W ~~EX~~  
1980 feet from ~~XXX~~ SE Corner of section 11e  
3300 feet from ~~XXX~~ SE Corner of section 11e

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Lease Name Kelly Well # 1

Operator: Petroleum Energy, Inc.  
Name & Address 415 First National Bank Building  
Wichita, KS 67202

County Stafford  
Well Total Depth 3830 124.48 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 17 Month: August Year: 1984

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3829' Perfs 3772-76'

1st plug sand back to 3722' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 pm Day: 17 Month: August Year: 1984

ACTUAL PLUGGING REPORT 5 1/2" set at 3829' Perfs 3772-76'

1st plug sanded back to 3722' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

8-24-84 AUG 24 1984

Maximum pressure 500 psi and shut in pressure 200 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired) observe this plugging.

DATE 8-27-84

Signed J. H. Metz  
(TECHNICIAN)

INV. NO. 3399