

To: 1 060987
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'E NW NE SE SEC. 9, T 24 S, R 11 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-27-87 15-185-21999-0000
API NUMBER 15-Completion Date 5/23/84
2310 feet from S section line
840 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8376
Operator: Striker Petroleum Corporation
Name & Address 5690 DTC Blvd., Suite 410
Englewood, CO 80111

Lease Name Figger Well # 4
County Stafford 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 27 Month: 7 Year: 19 87

Plugging proposal received from Ronny Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3898' PBTD 3867' Perfs at 3816-20' Elevation 1825' GL

1st plug sand back to 3765' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey and Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 10:30 a.m. Day: 27 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3765' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 450 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2610' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If ~~XXXXXX~~ observe this plugging.

DATE 7-29-87

INV. NO. 17648

JUL 29 1987

Signed

Paul A. Luthi
(TECHNICIAN)

Wichita, Kansas

07-29-87

FORM CP-2/3
Rev. 01-84