

1 080330

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,995-0000

NE NW NE, SEC. 9, T 24 S, R 11 W/X

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Sue Figger Well # 1

Operator: Kelso Casing Pulling

County Stafford

Name & Address Box 347

Well Total Depth 3840 ^{124 80} feet

Chase, KS 67524

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 20 Month: February Year: 19 85

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3839' Perfs at 3453' - 3680'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 am Day: 20 Month: February Year: 19 85

ACTUAL PLUGGING REPORT: 1st plug sanded back to 3400' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

03-04-1985
MAR 04 1985

Maximum pressure 400 psi and shut in 100 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2927' 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I (did / did not) observe this plugging.

DATE 3-7-85

Signed J. A. [Signature]
(TECHNICIAN)

INV. NO. 7242