

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-095-20976 0000

NW-NW-NW SECTION 32 TOWNSHIP 27 RANGE 5 W

OPERATOR LICENSE # 5086 4950 FEET FROM S SECTION LINE  
OPERATOR Pintail Petro. Inc. 4950 FEET FROM E SECTION LINE  
NAME 225 N. Market #300  
ADDRESS Wichita, KS. 67202 LEASE NAME: Wilson-Opdyke #1  
COUNTY Kingman  
WELL TOTAL DEPTH: 4650' 151.13  
PIPE: 4 1/2 @ 4287'  
SURFACE CASING 8 5/8 @ 259'

11/18

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD X D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Quality Well Service  
ADDRESS: Sterling KS. LICENSE: 31925

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntrye  
COMPANY NAME: Quality Well Service PHONE: 316-727-3410  
WERE: Open Hole- 4398-4650  
Sand back open hole to 4350 and cap with 4 sks of cement.  
Recover pipe.  
Spot 35 sks of cement at 850'  
Circulate cement from 350'-0'

PLUGGING PROPOSAL RECEIVED BY: Butch Hoeberecht

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (\_\_\_\_\_) PART (X) NONE (\_\_\_\_\_)  
COMPLETED: HOUR: 1115 DAY: 18 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT: The open hole was sanded back to 4112' and capped with 4 sks of cement. The pipe was shot loose at 1890' and pulled to 850, where 35 sks of cement was spotted. The pipe was pulled to 350' where cement was circulated to surface. The remaining pipe was pulled, and it was discovered that the pipe was part at 2140'. Cement were deeper than expected. Cement dropped to 180'. Tubing was run to 180' and cement was again circulated to surface.

REMARKS: United cementing #'s 1564& 1563 60/40 4% gel

**INVOICED** I DID ~~NOT~~ OBSERVE THIS PLUGGING.

RECEIVED  
KANSAS CORPORATION COMMISSION

DATE 1/19/00 Steve VanGieson  
WV. NO. 161134

Steve VanGieson

FORM CP-2/3  
REV. 3/90

JAN 18 2000

CONSERVATION DIVISION  
WICHITA, KS

(R)