

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 100-2

LOCATION CE/2 - SE - SE

SEC. 4 TWP. 24 RGE. 11-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Albert Crist

Operator Deep Rock Oil Corp Address Box #429 - Hutchinson - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3775 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 546 ft - Circulated with cement.  
4 1/2" casing set at 3700 ft - Filled back from bottom  
to 3750 ft with chat - Dumped 3 sacks of cement in  
the 4 1/2" casing at 3700 ft - Shot off & Pulled the 4 1/2" casing -  
Filled with mud to 2500 ft - Rock Bridge & 15 sacks of cement  
at 2500 ft - Mud to 30 ft - Plug & 10 sacks of cement  
at the surface - Bill Morgan - Plugging Contractor

**PLUGGING**  
WELL NO. 4-1-111  
DATE 7-9-49

C. M. Stoughton  
District Conservation Agent  
Date 7-9-49  
Conservation Div.

JUL - 9 1949  
STATE CORPORATION COMMISSION  
7-9-49