

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 130-2LOCATION NE-SW-NESEC. 7 TWP. 24 RGE. 11Dry Hole Abandoned Oil Well ☒ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease RansonOperator Columbia Supply, Co. Address Box 293, St. Bend, Ks.Field County StaffordTotal Depth 3795 Feet.Plugging Contractor Forbes Casing Pulling Co.Plugging Contractor's License No. 49Address Great Bend, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 286' C.W.C. 5 1/2" O.D. set 3784'
up 100 ss cem. Sanded hole to 3760 dump
5 ss cem. Shot off and pulled 5 1/2" casing
mudded hole to 275' set rock bridge and
dumped 25 ss cem. mud to 25' rock bridge
and 10 ss cem. to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1955

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date July 17, 1955