

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-3
LOCATION C2/2 NW SW
SEC. 9 TWP. 24 RGE. 11W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Figure 4
Operator West Supply Co. Address Chate - Kansas
Field _____ County Stafford
Total Depth 3813 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 273 ft. Circulated with cement.
5 1/2 casing at 3808 ft. Plugged back from bottom to
3015 ft with mud & Chet - Dumped 3 sacks of cement
at 3015 ft - Shot off & Pulled the 5 1/2 casing. Filled with
mud to 273 ft - Set Rock Bridge & 15 sacks of cement
at 273 ft - Mud to 30 ft - Plug & 10 sacks of cement at
the surface - Plugging Contractor - West Supply Co
West Supply Co - Bought this Well from Sunray Oil Corp

3-20-50

PLUGGING
FILE NO. 9-24-11W
BOOK PAGE 144-16

FILE NO. 9-24-11W
BOOK PAGE 144-16

District Conservation Agent

Date

3-16-50

C. H. Stough -