

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5271 EXPIRATION DATE July 1, 1985

OPERATOR Louis Kahan dba S & K Oil Co. API NO. 15-155-20904-6000

ADDRESS P.O. Box 559 COUNTY Reno ~~20309~~ (cannot read)

Tulsa, Ok. 74101 FIELD Burrton

** CONTACT PERSON A.D. BROWN PROD. FORMATION Lo. Miss.

PHONE 918-587-4159

PURCHASER NONE LEASE Miller

ADDRESS --- WELL NO. 5

DRILLING B & B DRILLING, INC. WELL LOCATION E/2 E/2 NW

CONTRACTOR 515 Union Center 330 Ft. from East Line and

ADDRESS Wichita, Ks. 67202 1320 Ft. from North Line of

the NW (Qtr.) SEC 10 TWP 24 RGE 4W.

11-30-84
 RECEIVED
 STATE CORPORATION COMMISSION
 NOV 30 1984

PLUGGING None

CONTRACTOR ---

ADDRESS ---

WELL PLAT

	#5		
		10	

(Office Use Only)

KCC

KGS

SWD/REP

PLG.

TOTAL DEPTH 3450 PBTD ---

SPUD DATE 12/4/82 DATE COMPLETED 11/28/84

ELEV: GR 1468 DF 1474 KB 1476

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE SWD

Amount of surface pipe set and cemented Well, 265 DV Tool Used? ---

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other ---

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

ALFRED D. BROWN, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Alfred D. Brown
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 27th day of November, 19 84.

Roberta D. Robinson
(NOTARY PUBLIC)
Roberta D. Robinson

MY COMMISSION EXPIRES: February 17, 1984

** The person who can be reached by phone regarding any questions concerning this information.

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Louis Kahan

LEASE Miller #5

SEC. 10 TWP. 24 RGE. 4W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	2381	-905		
Brown Lime	2556	-1080		
Lansing	2578	-1102		
B K C	3019	-1543		
Cherokee	3154	-1678		
Mississippi	3293	-1817		
R.T.D.	3383	-1907		
Cable Tools to T.D.	3450	-1974		

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	10-3/4"		265	Pos-Mix	320	---
Production	7-7/8"	5 1/2"	14#	3382	Common	150+	2% cc.
						to surf	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					
TUBING RECORD			Open Hole		3383 -3450'
Size	Setting depth	Packer set at			
2-7/8 F.G.	3325	3325			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal 15% N.E. Acid	OPEN HOLE

Date of first production: <u>Disposal</u> <u>11/28/84</u>	Producing method (flowing, pumping, gas lift, etc.) -----	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil ----- bbis.	Gas ----- MCF
	Water %	Gas-oil ratio ----- CFPB
Disposition of gas (vented, used on lease or sold)		Perforations