

WELL PLUGGING RECORD

Stafford County. Sec. 9 Twp. 24 Rge. 11 (E) (WX)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CE $\frac{1}{2}$ NW SW
Lease Owner West Supply Company
Lease Name Figger Well No. 1
Office Address Box 506, Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed. 1/27/50 19
Application for plugging filed. 19
Application for plugging approved. 19
Plugging commenced. 1/21/50 19
Plugging completed. 1/27/50 19
Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?..... yes

Name of Conservation Agent who supervised plugging of this well.....Durkee.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Rocked hole from 3163 to 2980. Run
5 sacks of cement. Mudded to 270.
Made rock bridge at 270. Run 15 sack
of cement at 277. Run 10 sacks at 30.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
H. I. Herbel (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

(Address

SUBSCRIBED AND SWORN to before me this 22nd day of April, 1950

My commission expires.....Dec. 5, 1950.

Elmer A. Schulke - - - Notary Public.




WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. TRANSWESTERN OIL CO.
Farm. G.W.Figger No. 1.

SEC. 9 T. 24 R. 11 W
C E₁ NW SW

Total Depth. 3813'
Comm. 4-19-44 Comp. 5-23-44
Shot or Treated.
Contractor.
Issued. 7-8-44

County. Stafford
KANSAS



CASING:

9" 273' Cem.
5 1/2" 3808' Cem.

Elevation. _____

Production. Pot. 55 B.

Figures Indicate Bottom of Formations.

sand	120
red bed	380
red bed & shale	614
anhydrite & shale	675
shale & shells	1135
salt & shale	1250
shale & shells	1440
shale	1500
lime broken	1550
lime	1610
lime & shale	1730
lime	1830
lime & Shale	1840
lime sandy	1980
lime & shale	2095
lime broken	2265
shale & lime	2345
lime broken	2385
shale	2425
shale & lime	2795
lime broken	2870
lime	2935
shale	2948
lime	3215
shale	3250
lime	3280
shale	3305
shale & lime	3385
shale	3425
lime	3502
lime & chert	3530
lime & shale	3745
shale	3806
lime	3810
cable tools	
lime	3813
Total Depth.	
Tops: Heebner	3229
Lansing	3412
Viola	3807

APR 13 1950

