


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 10 Twp. 24 Rge. (E) 111 (W)
Location as "NE/CNW&SW&" or footage from lines C E 1/NW/SE
Lease Owner Columbia Supply
Lease Name Mary Banker Well No. C 1
Office Address Box 293, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 4-30-56 19____
Plugging completed _____ 5-16-56 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3812 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		2877.66'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged started 4-30-56 and completed 5-16-56. Measured in to TD 3760'.
Plugged off bottom with 31' of rock and dumped in 6 sacks of cement.
Worked pipe. Shot well casing at 2900'. Circulated and spotted oil with 60 bbls. Filled hole with heavy mud and built permanent rock bridge at 250'. Dumped in 25 sacks of cement and filled hole with heavy mud. capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes, d/h/a/ Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) J. O. Forbes
(Address) 221 Great Bend,

SUBSCRIBED AND SWORN TO before me this 17 day of May, 1956
My commission expires April 8, 1957
Arthur Ziskel Notary Public.

PLUGGING
FILE SEC. 10 T. 24 R. 11w
BOOK PAGE 57 LINE 8

STATE CORPORATION COMMISSION
MAY 29 1956
WICHITA, KANSAS

Sunray Mid-Continent Oil Company
Great Bend, Kansas

April 25, 1956

Drilling Contractor: Iron Drilling Company
Drilling Commenced: 6-9-40
Drilling Completed: 7-9-40

Mary Banker C-1
C EL-NW-SE
Section 10-24-11, Stafford Co., Kans

DRILLERS LOG

Surface	165	Shale & Shells	2625
Red Bed & Shale	190	Lime	2647
Shale & Shells	270	Shale & Shells	2693
Shale & Red Bed	513	Lime Brown	2719
Hyd	537	Shale	2767
Shale & Shells	1060	Lime & Shale	2783
Shells & Salt	1077	Lime	2803
Salt	1285	Shale	2833
Shale & Salt	1325	Lime	2845
Shale & Lime	1528	Shale	2863
Lime Broken	1615	Lime	2883
Lime & Shale	1628	Shale & Shells	2905
Cherty Lime	1650	Lime & Chert	2922
Lime & Shale	1695	Lime	3020
Brown Chert	1698	Shale	3026
Lime & Shale	1760	Lime	3124
Lime	1775	Shale & Lime	3135
Lime & Shale	1795	Lime	3185
Lime	1815	Lime & Shale	3256
Shale & Shells	1880	Lime & Shale & Red Bed	3322
Lime Broken	1936	Shale & Red Rock	3370
Broken Lime & Shale	1942	Shale	3395
Lime	2010	Lime	3415
Lime Broken	2030	Lime & Shale	3477
Shale	2040	Shale & Cherty Lime	3496
Lime	2084	Lime	3509
Lime & Shale	2125	Broken Lime	3520
Shale & Shells	2149	Lime & Chert	3547
Broken Lime	2171	Lime & Shale	3635
Shale & Shells & Red Bed	2225	Lime & Chert	3696
Shale & Shells	2385	Shale	3708
Shale & Shells	2400	Shale & Chert	3744
Shale & Shells	2470	Shale & Lime	3760
Lime	2495	Lime	3812
		Top of Viola Lime	3757'
		Total Depth with Rotary	3760'

I hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Mary Banker C-1, CEL-NW-SE, Section 10-24-11, Stafford County, Kansas, to the best of my knowledge.

H. E. Housh
Notary Public

December 24, 1956
My Commission Expires

N. E. Montgomery
N. E. Montgomery

RECEIVED
APR 25 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 10-24-11W
BOOK PAGE 57 LINE 8