


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Pitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 10 Twp. 24 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines CEL - NE - SE  
Lease Owner Sunray Oil Corporation  
Lease Name Banker "A" Well No. #1  
Office Address Box 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed January 26, 1940  
Application for plugging filed September 15, 1952  
Application for plugging approved September 16, 1952  
Plugging commenced October 7, 1952  
Plugging completed October 15, 1952  
Reason for abandonment of well or producing formation No longer economical

If a producing well is abandoned, date of last production September 8, 1952  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merl Rives, Box 207, Great Bend, Kansas  
Producing formation Missner - Viola Depth to top 3720' Bottom 3806' Total Depth of Well 3806 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Missner Sd.	Oil	3720'	3724'	7"	3754'	1789'
Viola	Oil	3754'	3777'			
Surface hole		0	241'	10-3/4"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole to 3310' and ran 6 sacks of cement.  
Bailed hole, and mudded hole to 250'. Set 10'  
rock bridge, and ran 20 sacks of cement. Mudded  
hole to 20' and ran 10 sacks of cement on top.  
Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply  
Address Chase, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.  
Buddie E. Livingston (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Buddie E. Livingston  
Box 195, Great Bend, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1952.

Martha Scott  
Notary Public.

My commission expires 4/19/56

24-2675-S 2-52-20M

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1952

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
INDEX SEC 10 T 24 R 11 S  
BOOK PAGE 45 LINE 5

SAMPLE LOG

FORMATION	TOTAL DEPTH
Surface	252
Red Bed & Shells	315
Red Bed & Shells	510
Hyd & Shale	535
Shale	625
Red Bed & Shale	1005
Salt	1075
Shale & Shells & Salt	1085
Shale & Shells & Salt	1255
Shale & Shells & Red Bed	1445
Shale & Shells & Lime	1515
Lime	1565
Lime	1637
Lime & Shale	1720
Broken Lime	1777
Lime	1850
Lime & Shale	1875
Porous or Rotten Lime	1900
Lime & Some Shale	1945
Lime & Shale	2000
Lime	2031
Lime & Shale	2542
Broken Lime & Shale	2595
Shale & Shells	2623
Broken Lime	2682
Lime & Shale	2932
Lime	2966
Lime & Some Shale	3024
Lime & Shale	3069
Lime	3206
Lime & Shale	3500
Lime	3505
Lime And Some Streaks Of Shale	3556
Lime	3667
Chert	3695
Lime	3727
Pyrite & Chert	3731
Cored	3764
Lime & Chert	3772
Cored	3787
Lime & Chert	3794
Cored (Total Depth)	3806

STATE OF KANSAS, COUNTY OF BARTON, ss.

I, Buddie E. Livingston, do hereby certify that the above is a true and accurate copy of the Sample Log on the Banker "A" - #1, Located in the SE/4, Sec. 20, Twp. 24, Range 11 West.

Buddie E. Livingston

Subscribed and sworn to before me this 2nd day of October, 1952.

Martha Scott  
Notary Public

My commission expires 4-19-56.

