

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Stafford County, Sec. 10 Twp. 24 S Rge. (E) 11 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C N/2 S/2 NW/4

Lease Owner Stanolind Oil & Gas Co.

Lease Name R. V. Richardson Well No. 5

Office Address Box 591 Tulsa Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed Mar. 29 19 41

Application for plugging filed Aug. 19 19 47

Application for plugging approved Aug. 20 19 47

Plugging commenced Oct. 4 19 47

Plugging completed Oct. 26 19 47

Reason for abandonment of well or producing formation No longer productive

If a producing well is abandoned, date of last production July 31 19 47

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.

Producing formation Viola Depth to top 3749 Bottom 3788 Total Depth of Well 3788 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil	3749	3788	10 3/4	272	None
				5 1/2	3770	2906

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 3734 to 3694 feet to 260 to 240 feet for each plug set.

Filled with mud from 3788' to 3734'. Dumped 5 sacks cement, filled from 3734' to 3694'. Ripped casing at 2920' and pulled. Filled with mud from 3694' to 268'. Dumped 15 sacks cement, filled from 268' to 240'. Filled with mud from 240' to 15'. Dumped 10 sacks cement, filled from 15' to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stanolind Oil & Gas Co.
Address Box 518 Zenith Kansas

STATE OF Kansas COUNTY OF Stafford, ss.
Blayden (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Blayden

Zenith Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of November 19 47

My Commission Expires Dec. 20, 1947

My commission expires. W. J. Johnson Notary Public.

NOV - 6 1947

PLUGGING
FILE SEC 10 T 24 R 11 W
BOOK PAGE 127 LINE 8

FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Cellar	0	5			
Sand & clay	5	155			
Red bed	155	300			
Red bed & sand	300	529			
Anhydrite	529	560			
Shale	560	830			
Shale & Shells	830	1100			
Salt & shale	1100	1150			
Shale & shells	1150	1230			
Shale	1230	1395			
Lime	1395	1415			
Shale & Shells	1415	1480			
Broken Lime	1480	1698			
Lime	1698	1720			
Broken Lime	1720	1980			
Shale & lime shells	1980	2040			
Broken lime	2040	2130			
Shale	2130	2265			
Broken lime	2265	2305			
Shale	2305	2335			
Broken lime	2335	2380			
Shale	2380	2580			
Broken lime	2580	2610			
Shale	2610	2800			
Broken lime	2800	3055			
Lime	3055	3220			
Shale	3220	3395			
Lime	3395	3705			
Shale	3705	3749			
Dolomite	3749	3756			
Lime	3756	3762			
Dolomite & lime	3762	3767			
Lime	3767	3769			
Dolomitic Lime	3769	3778			
Dolomite & chert	3778	3781			
Dolomite	3781	3788			
<u>Total Depth</u>		<u>3788</u>			

15-185-10189-0000



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

November 3, 1947

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Standard Oil & Gas Co.
Box 515
Zenith, Ka.

Dear Sir:

IN ACCOUNT WITH Conservation Division, State Corporation Commission
Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ 25.00.

Well No. 5
Farm R. V. Richardson
Description NW SE NW 10-24-11W
County Stafford
File: 127-8

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due December 7, 1947

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a Well Plugging Record on this well to complete our file.

#715349
Paid
12-5-47
JB